

# *“ERTMS accredited labs: A powerful tool for performing Components and System Compatibility Tests”*

ERTMS Accredited Laboratories (EAL)



Dr. Eng. I.J. Iglesias

# Type of Tests performed at EAL labs

## 1.- Components:

- **On-board Conformity Tests** - According to TSI standard specifications (Subset-076, Subset-094,...)- BTM, EVC
- **Trackside Conformity Tests** – According to TSI standard specifications (Subset-085, Subset-103,...)- Eurobalise, Euroloop
- **Other developments - “Subset -TRK”**: covering requirements from trackside constituents (RBC - IXL)

## 2.- System Tests:

- **Operational Tests Scenarios (OTS)** – Operational test scenarios based on Engineering Rules of the ETCS trackside as part of trackside subsystem EC Verification/certification process.
- **ESC Tests** – To increase system confidence and assure ETCS system compatibility between trackside and a new On-board Subsystem to operate in a certified line.

Lab Testing in the frame of  
(EU) 2016/919 CCS TSI  
(amended by EU 2019/776)

# Lab Testing in the frame of 2016/919 EU CCS TSI (amended by EU 2019/776)

(10) “Even a successful certification process cannot always exclude that, when an on-board CCS subsystem interacts with a trackside CCS subsystem, one of the subsystems repeatedly fails to function or perform as intended under certain conditions..... Therefore, checks might need to be carried out to demonstrate the technical compatibility ..... **The possibility of executing those checks in a laboratory representing the trackside configuration to be made available by the Infrastructure Manager should be prioritized**”

## Examples of ETCS System Compatibility checks

- MRSP Supervision
- Braking Curves supervision
- Baseline Compatibility Assessment (BCA)
- SPAD
- Commercial itineraries
- Level Transitions
- Mode Transitions
- TSR management
- MA (EoA, Timers in L1...)
- Track Conditions
- Confidence interval impact.
- Driver operational actions
- Maximum permitted speed in the line.
- Degraded conditions
- Handover


Representative Configuration of the  
On-Board Unit

# Lab Testing - OTS & ESC Tests

- **Facility** - It operates as a Test Center contracted by the IM and/or in agreement to OB|TS suppliers
- **Test architecture** - Modular approach - Precision, flexibility and credibility of the lab structure - All labs are compatible with SS-094 architecture. Capability to be adapted to different architectures (e.g. SS-111) as well as different track data formats (S-112, RailML...)
- **Test Procedure** - Defines the process to be followed


# Lab Testing - OTS & ESC Tests

## Test Architecture



# Lab Testing - OTS & ESC Tests


- **Test Procedure** - Preparation phase: Track data Importation



Database Storage

## Project Track Data Loading into Test Bench


- Topology
- Set of Routes
- Track elements



# Lab Testing - OTS & ESC Tests

## Test Procedure - Preparation phase: OTC (Generic application)

### Operational Test Cases



- Set of OB and TS events reproducing the expected operational behavior according to applicable Project Engineering Rules/ETCS functionality.
- Traceability OTC - Engineering rules requirements to verify the proper fulfilment.

### Database Storage


TEST CASE DESCRIPTION			
Test case	Code	Version	Title
	Opp. 2.4.2.1	0.4	Mode transitions inside the upgrade window of a signal/marker board (PCA). PROCEED mode is established. Transition from GR to FS mode.
Trackside "Baseline" application / Operator baseline application			
Baseline 2 (2.3.0.0) / Baseline 3 (3.0.0.0)			
Test case author			
Verify that once the train is detected with the min safe front and inside the PCA window (a position report inside the PCA is received by the RBC), the RBC provides the MA and Train Description and Countdown commands the transition from GR to FS mode.			
Test objective(s)			
Based on specific requirements			
2.4.2.1, 2.4.1.1, 1.3, 1.3.3			
Diagram			
Starting conditions			
Level:	2		
Mode:	GR		
Train:	NR		
Speed (km/h):			
Actions starting conditions:	The train is approaching the signal/marker board giving PROCEED aspect.		
Sequence of the Test Case	RBC Communication session is established.		
Checkpoints			
Step	Step description	Interfaces	OKY
1	Train is approaching the signal showing PROCEED aspect. Note: If train is located inside the PCA this step shall be checked with train at standstill.	INF	Train is moving (V_TRAIN=V)
2	The EVC sends a position report indicating that it is inside the PCA area.	DMI (O) - JRU	MESSAGE TO RBC (IND_MESSAGE_JRU=10; IND_MESSAGE=33; IND_PACKET=0; Q_DRLRBC=C; Q_DRLRBC=C; M_MOROC=1) is received
3	The RBC "allows" movement. -CSD monitoring type and Red supervision status with permitted speed supervision limit Pn = V_MAXPn (STAT) is received. National values are provided by the RBC.	DMI (O) - JRU	SPRINT/RED/MOT is displayed -CSD monitoring type and Red supervision status with permitted speed supervision limit Pn = V_MAXPn (STAT) is displayed Data grey

CEDEX	ERTMS Level 2 Operational Test Cases for laboratory testing: Trace RBC of the Train Clear order	Date: 19/09/2016 Version: 0.1
-------	---	----------------------------------

Train is moving (V_TRAIN = V_MAXPn). The speed and distance monitoring information is displayed. Note: In case the LRBC is in advance of the train front end the RBC shall send the MA by means of message 33.	JRU	MESSAGE FROM RBC (IND_MESSAGE_JRU=9; IND_MESSAGE=33; IND_PACKET=21; IND_PACKET=27) is received	RBC
	JRU	MESSAGE FROM RBC (IND_MESSAGE_JRU=9; IND_MESSAGE=33; IND_PACKET=21; IND_PACKET=27) is received	RBC
	JRU	SPRINT AND DISTANCE MONITORING INFORMATION (IND_MESSAGE_JRU=8; M_SDMT=0; M_SDMGUPSTAT=0) is received	RBC
4 The EVC reports to the RBC the train position	DMI (O) - JRU	MESSAGE TO RBC (IND_MESSAGE_JRU=10; IND_MESSAGE=33; IND_PACKET=0; Q_DRLRBC=C; Q_DRLRBC=C; M_MOROC=1) is received	RBC
Final state	Level:	2	
	Mode:	FS	
	Train:	NR	
	Speed (km/h):		


# Lab Testing - OTS & ESC Tests

## ▫ Test Procedure - Preparation phase: Circulations



Database Storage

- ✓ Set of route combination (PROCEED, OS, SH...)
- ✓ Operational actions
  - DMI inputs (Driver)
  - Signalman
  - Relevant driving actions (SPAD / Overspeed, Stop...)





# Lab Testing - OTS & ESC Tests

- Test Procedure - Preparation phase: OTS (Specific application)


OTS_Name	Circulation_ID	OTC_CODE	TrackElementType(S)	TrackElement_ID(S)	Offset(S)	TrackElementType(E)	TrackElement_ID(E)
LIN_Supervision	10	<a href="#">OPP-2.1.7</a>	Balise Group	1338	0	Balise Group	1338
SSP_Supervision	10	<a href="#">2.3</a>	Point	5003a	0	Point	5003a
SSP_Supervision	10	<a href="#">24.1 c</a>	Point	505b	0	Point	505b
PCA_SAD_FS	10	<a href="#">OPP-2.4.3</a>	Signal	S5035	0	Signal	S5035
EoA_Supervision	10	<a href="#">OPP-2.6.2.2</a>	Signal	S5035	0	Signal	S5035
SoM_SB_SR	11	<a href="#">OPP-2.2.1.2.1/OPP-2.13.2.3_b</a>	Signal	SRP2013	-	Signal	SRP2013
PCA_SR_FS	11	<a href="#">OPP-2.4.2.1</a>	Signal	S2013	-50	Signal	S2013
PCA_CES	11	<a href="#">OPP-2.4.4</a>	Signal	S2013	25	Signal	S2013
TSR_80_FS	11	<a href="#">OPP-2.1.8_d</a>	TSR	Kp 0.500	0	TSR	KP 1.500
SSP_Supervision	11	<a href="#">24.1 b</a>	Speed Change	KP 5.232	0	Speed Change	KP 5.232
SSP_Supervision	11	<a href="#">2.3</a>	Speed Change	KP 8.318	0	Speed Change	KP 8.318
SSP_Supervision	11	<a href="#">24.1 b</a>	Speed Change	KP 11.232	0	Speed Change	KP 11.232
SSP_Supervision	11	<a href="#">2.3</a>	Speed Change	KP 14.100	0	Speed Change	KP 14.100
SSP_Supervision	11	<a href="#">2.3</a>	Speed Change	KP 16.710	0	Speed Change	KP 16.710
SSP_Supervision	11	<a href="#">24.1 b</a>	Speed Change	KP 17.702	0	Speed Change	KP 17.702
SSP_Supervision	11	<a href="#">2.3</a>	Speed Change	KP 27.061	0	Speed Change	KP 27.061
SSP_Supervision	11	<a href="#">24.1 b</a>	Speed Change	KP 27.292	0	Speed Change	KP 27.292
SSP_Supervision	11	<a href="#">2.3</a>	Speed Change	KP 30.510	0	Speed Change	KP 30.510

## Operational Test Scenarios

- Placing OTC's on specific locations in the line where they can be tested according to the selected Circulation


# Lab Testing - OTS & ESC Tests

## Test Procedure – Execution & Analysis phase



After integrating real EVC and real RBC at lab, test are executed

Video of a Test execution



Logs registering DMI, TIU, TMS and JRU

Applications Places System Thu May 16, 15:07:58 operador

Route Map Controller

View Help

1966.87m 14:07:58 < S 1966.87m L 15:07:58 >

(JPEG Image, 640 x 480 pixels) - Scaled (91%) - Mozilla Firefox

192.168.100.52:9000/?action=stream

DDO

Time	Name	Comments
15-01-45.103	Sahara - Point Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = p5005b, GrpID/SubGrpID = 0/0, ADA=1, Locked=1, Right=1
15-01-45.174	Sahara - Point Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = p5004, GrpID/SubGrpID = 0/0, ADA=1, Locked=1, Right=1
15-01-45.191	Sahara - Point Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = p5002a, GrpID/SubGrpID = 0/0, ADA=1, Locked=1, Right=0
15-01-45.204	Sahara - Point Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = p5001b, GrpID/SubGrpID = 0/0, ADA=1, Locked=1, Right=1
15-02-36.959	Sahara - Signal Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = s5042, GrpID/SubGrpID = 0/0, ADA=1, CSO=0, ESO=0, EST=0
15-05-25.306	Sahara - Signal Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = s5042, GrpID/SubGrpID = 0/0, ADA=1, CSO=0, ESO=0, EST=0
15-06-10.974	Sahara - Signal Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = s5032, GrpID/SubGrpID = 0/0, ADA=1, CSO=0, ESO=0, EST=0
15-06-39.613	Sahara - Signal Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = s5032, GrpID/SubGrpID = 0/0, ADA=1, CSO=0, ESO=0, EST=0
15-06-57.959	Sahara - Signal Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = s5024, GrpID/SubGrpID = 0/0, ADA=1, CSO=0, ESO=0, EST=0
15-07-09.057	Sahara - Signal Status Report	TVS->DDO, ProjectID = 10, StationID = DDO, ElementID = s5024, GrpID/SubGrpID = 0/0, ADA=1, CSO=0, ESO=0, EST=0


DDO DKR RFQ SMR TRY Log

(JPEG Image, 640 x 480 pixels) [videos] operador@traffic2.2... operador@traffic2.2/Al... [videos - File Browser] Route Map Controller

# Lab Testing - OTS & ESC Tests

## Test Procedure - Execution & Analysis phase

OTS_Name	Circulation_I	OTC_CODE	TrackElementType	TrackElement_ID	TrackElementE	TrackElement_ID	Test Resu
SoM_SB_SR	8	OPP-2.2.1.2.1/OPP-2.13.2.3_b	Signal	SRP2017	Signal	SRP2017	OK
PCA_SR_FS	8	OPP-2.4.2.1	Signal	S2017	Signal	S2017	OK
PCA_CES	8	OPP-2.4.4	Signal	S2017	Signal	S2017	OK
SSP_Supervision	8	2.3	Point	2004	Point	2004	OK
SSP_Supervision	8	24.1 b	Point	2004	Point	2004	OK
SSP_Supervision	8	2.3	Point	2006a	Point	2006b	OK
SSP_Supervision	8	24.1 b	Point	2006b	Point	2006b	OK
SSP_Supervision	8	24.1 b	Speed Change	KP 5.232	Speed Change	KP 5.232	OK
SSP_Supervision	8	2.3	Speed Change	KP 8.318	Speed Change	KP 8.318	OK
SSP_Supervision	8	24.1 b	Speed Change	KP 11.232	Speed Change	KP 11.232	OK
SSP_Supervision	8	2.3	Speed Change	KP 14.100	Speed Change	KP 14.100	OK
SSP_Supervision	8	24.1 b	Speed Change	KP 14.099	Speed Change	KP 14.099	OK
SSP_Supervision	8	2.3	Speed Change	KP 16.710	Speed Change	KP 16.710	OK
SSP_Supervision	8	24.1 b	Speed Change	KP 17.702	Speed Change	KP 17.702	OK
TCO_Supervision	8	OPP-2.15.1	Powerless Section	KP 21.507	Powerless Section	KP 21.610	OK
TEX_Supervision	8	OPP-2.16.1	Commercial Station	KP 9.547_Thiaoye	Commercial Station	KP 9.547_Thiaoye	OK
TEX_Supervision	8	OPP-2.16.1	Commercial Station	KP 26.670_Rufisque	Commercial Station	KP 26.670_Rufisque	OK
TNV_Supervision	8	OPP-3.1.3.1	Signal	S3001	Signal	S3001	OK
NVA_T_INVCONTACT	8	OPP-2.1.9	Signal	S3001	Signal	S3001	OK
LBG	8	OPP-3.3.1	Balisse Group	1103	Balisse Group	1105	OK
OVR_FS	8	OPP-2.10.3 a	Balisse Group	1105	Balisse Group	1105	OK
PCA_SR_FS	8	OPP-2.4.2.1	Signal	S3007	Signal	S3007	OK
PCA_CES	8	OPP-2.4.4	Signal	S3008	Signal	S3008	OK
EoS_FS	8	OPP-2.8.2.1 a	Signal	S4023	Signal	S4023	OK
EaA_Supervision	8	OPP-2.6.2.2	Topera	T_Rufisque	Topera	T_Rufisque	OK
STP_BufferStop	8	OPP-2.11.2	Buffer Stop	T_Rufisque	Buffer Stop	T_Rufisque	OK
LIN_Supervision	8	OPP-2.1.7	Balisse Group	1008	Balisse Group	1008	OK
LIN_Supervision	8	OPP-2.1.7	Balisse Group	1013	Balisse Group	1013	OK
LIN_Supervision	8	OPP-2.1.7	Balisse Group	1015	Balisse Group	1017	OK
LIN_Supervision	8	OPP-2.1.7	Balisse Group	1017	Balisse Group	1017	OK
LIN_Supervision	8	OPP-2.1.7	Balisse Group	1019	Balisse Group	1019	OK
LIN_Supervision	8	OPP-2.1.7	Balisse Group	1029	Balisse Group	1029	OK





TEST CASE DESCRIPTION			
Test Case	Code	Version	Title
Opp-2.4.2.1	0.4		Mode transitions mode the upgrade window of a signal/marker board (PCA) PROCEDURE route is established. Transition from SR to FS mode
Trackside Baseline applicable	Baseline 2 (2.3.0.1)		
Test case author	Baseline 2 (2.3.0.1)		
Test Objective(s)	Verify that once the train is detected with the min safe front end inside the PCA window a positive report inside the PCA is received by the RBC. The RBC provides the BA and Track description and DTMG commands the transition from SR to FS mode.		
Test or specific requirements	2.2.2.1, 2.4.1.1, 2.3.3		
Level	2		
Mode	SR		
Train Speed limits	N/A		
Additional starting conditions	The train is approaching the signal/marker board along PROCEDURE route. Radio Communication session is established.		
Interfaces			
INTE	Train is moving (V_TRAIN=V)		
DM (O)	MESSAGE FROM TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 Q_ID_RBC=0; M_MODE=0 is received		
DM (O)	MESSAGE FROM RBC TO RBC IND_PACKET=13 IND_PACKET=21 Q_ID_RBC=0; M_MODE=0 is received		
DM (O)	MESSAGE FROM RBC TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 Q_ID_RBC=0; M_MODE=0 is received		
DM (O)	MESSAGE FROM RBC TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 Q_ID_RBC=0; M_MODE=0 is received		
DM (O)	MESSAGE FROM RBC TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 Q_ID_RBC=0; M_MODE=0 is received		

CEDEX	ERTMS Level 2 Operational Test Cases for laboratory testing - Thava RBC of the TGV-Dakar project	Date: 19/09/2019 Version: 0.1
-------	--	----------------------------------

Train is moving (V_TRAIN=V) (SR/FS)	JRU	MESSAGE FROM RBC TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 IND_PACKET=27 is received	RBC
The speed and distance monitoring information is received.	JRU	MESSAGE FROM RBC TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 IND_PACKET=27 is received	RBC
Note: In case the LRBG in advance of the train front end the RBC shall send the message 35	JRU	MESSAGE FROM RBC TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 IND_PACKET=27 is received	RBC
4 The RBC reports to the RBC the train position	DM (O)	MESSAGE FROM RBC TO RBC IND_MESSAGE_JRU=0 IND_PACKET=13 IND_PACKET=21 Q_ID_RBC=0; M_MODE=0 is received	RBC
Final state	Level	FS	
	Mode	FS	

# Lab Testing - OTS & ESC Tests

- **Independency** on Test Report from ETCS suppliers, specially relevant if different ETCS TS – OB suppliers
- **Trust and confidence** when transferring tests from track to Lab - Lab intercomparisson




- **Experience** more than 16 real L1 and L2 lines already tested at EAL

# Lab Testing - OTS & ESC Tests



Setting routes, TSR

**Panoramic view of a EAL: a ESC Test Campaign of a real line with two RBCs and one EVC**



Real train antenna for balise messages

# Lab Testing - OTS & ESC Tests



# Conclusions

- Lab Testing is a powerful tool in the “**Digital Transformation of Railways System**”
- Lab testing strongly simplifies the process of executing Operational Test Scenarios and System Compatibility Tests among different On-board and Trackside subsystems suppliers.
- Having a “**Digital Twin**” of a ETCS track in the lab allows in terms of OTS and ESC tests:
  - To be part of a whole **Test process** - Any scenario in nominal or degraded conditions can be reproduced dynamically in the Lab using both TS and OB ETCS subsystems.
  - To set the basis of **Digital Information Exchange System** for the Register and Maintenance of **ETCS RINF** of the (Trans)European Network, ready at any moment to perform ESC Tests when a new On-board of a vehicle is approved.
  - **Flexibility - In Advance Debugging:** compatibility issue detection and change management is fast and does not need the corresponding Safety Case analysis - Avoiding “*last minute*” functionality problems
- Cost of testing will be strongly reduced by executing OTS and ESC tests at lab. It is the only way of addressing this issue in a future European ETCS network.
- EAL has a wide experience in performing OTS and ESC tests at lab. More than 16 real lines have been already tested.



# Thank you for your kind attention

*EAL: ERTMS Accredited Labs*



**CEDEX**  
CENTRO DE ESTUDIOS  
Y EXPERIMENTACIÓN  
DE OBRAS PÚBLICAS



**SNCF** Rapprochons-nous  
Ingénierie du Matériel

LEF: Laboratoire  
ERTMS France

**Multitel**  
INNOVATION CENTRE

